

Ballasted mounting ideal for brownfields, landfills, and rooftops.




# **3 STEP INSTALLATION**

- 1. Lay out supports
- 2. Connect with rails
- 3. Fasten modules to rails



# 1PART, 3 FUNCTIONS

- -• Wind deflector
- Ballast tray —



### **SYSTEM HIGHLIGHTS**

- Ideal for brownfields and landfills
- Reduced maintenance
- Low \$/W
- 10 year warranty
- Low point loading
- 2-3 week lead time
- P.E. signed sealed permitting documents for every job
- Adapts to complex array shapes
- Manufactured in USA including Puerto Rico

### **DESIGN**

- Fully modular
- 5 to 25 degree tilt angles
- Sleek, low profile preferred by townships
- Each system custom fabricated

# **CONTACT US**

Solstice Manufacturing Co. 270 South Main Street Suite 102 Flemington, NJ 08822

Phone: 908 . 284 . 0096

www.solsticemanufacturing.com

info@solsticemanufacturing.com



### **SOLSTICE SPECIFICATIONS**

Average Overall Weight | 4.6 lt

4.6 lbs. per square foot

Tilt Angles

5°, 7.5°, 10°, 12.5°, 15°, 20°, 25° (Custom angles available upon request)

Material

5052-H32 aluminum alloy supports with stainless steel fastening hardware. 6063-T6 aluminum alloy rails

Application

Roof or ground systems

Grounding

Wiley WEEB clips or equivalent

Module Compatibility

Most major brands

Installation Rate

4 Person Crew can install 240-320

mounting supports per day

Testing

CFD and wind tunnel tested

Warranty

Standard 10 years

Manufacturing Location

All Solstice components are made in USA

